


STORM WATER MANAGEMENT PLAN



TWELVEMILE CREEK VOLUME 14 ERIE COUNTY DEPARTMENT OF PLANNING COMMONWEALTH OF PENNSYLVANIA



TD
665
.S76
1981
V14
C1

OCTOBER 1981
PREPARED BY
NORTHWEST INSTITUTE OF RESEARCH - WOODRUFF, INC.
AS A CONSORTIUM

WATERSHED ADVISORY COMMITTEE

Member

Joyce Andrews
Delores Bendig
Gerald Blanchfield
Harold Crane, Jr.
Frank Fenton
John Gresch
LeRoy Gross
Ted Guzzy
Richard P. Hessinger
John Klier
Earl Koon
Roger C. Latimer
Rose Little
Jacob Luke
Kenneth Maas
Paul Martin
Wasinder Mokha
Jeanne O'Brien
Wilbur Osborn
Lawrence Pieper
Norman H. Rabell
Mary B. Ripley
Robert Smith
Ronald VanTassell
Larry Wygant

Representing

Lake City Borough
Lawrence Park Township
Harborcreek Township
Elk Creek Township
North East Township
Platea Borough
Erie County Conservation Dist.
Girard Township
Summit Township
Fairview Township
Washington Township
Fairview Borough
McKean Township
Greenfield Township
North East Borough
Millcreek Township
Erie City
McKean Borough
Waterford Township
Franklin Township
Conneaut Township
Wesleyville Borough
Greene Township
Springfield Township
Girard Borough

ERIE COUNTY DEPARTMENT OF PLANNING

David Skellie	Acting Director
Thomas DeBello	Senior Planner
Jeffrey Spaulding	Transportation Planner
Gilbert Rocco	Project Planner
A. Latif Panhwar	Planning Analyst
Dolores Oblinski	Draftsman II
Lori Prody	Executive Secretary
Kathleen Anderson	Secretary

This study was financed through a planning assistance grant from the National Oceanic and Atmospheric Administration as administered through the Pennsylvania Department of Environmental Resources Coastal Zone Management Office (Office of Resources Management), and the Erie County Department of Planning.

STORM WATER MANAGEMENT PLAN /
TWELVEMILE CREEK WATERSHED

Volume 14

Prepared For
Commonwealth of Pennsylvania
Department of Environmental Resources
and
Erie County Department of Planning

Prepared By
Northwest Institute of Research - Woodruff, Inc.
As a Consortium

October 1981

TD665 .S76 1981 v.14 c.1
#32967194

TABLE OF CONTENTS

		<u>Page</u>
Section 1	SUMMARY AND RECOMMENDATIONS	1-1
Section 2	BACKGROUND	2-1
Section 3	DESCRIPTION OF THE TWELVEMILE CREEK WATERSHED	3-1
3.1	Local Input Data	3-1
3.1.1	Significant obstructions	3-1
3.1.2	Existing drainage problem areas	3-2
3.1.3	Existing storm sewers	3-3
3.1.4	Proposed storm sewers	3-3
3.1.5	Existing and proposed flood control projects	3-3
3.2	Present and Projected Land Use	3-3
3.3	Soil Types	3-4
3.4	The National Flood-Insurance 100-Year Flood Plain	3-4
Section 4	STANDARDS AND CRITERIA FOR STORM WATER MANAGEMENT	4-1
4.1	Definition of Design Storm	4-1
4.2	Definition of Type 1 and Type 2 Channels	4-1
4.3	Criteria for Type 1 Channels (Main Stream)	4-2
4.4	Criteria for Type 2 Channels (Branch Streams)	4-2
Section 5	IMPLEMENTATION	5-1
5.1	Introduction	5-1
5.2	Special Considerations	5-1
5.3	Building Permit Process	5-2
5.4	Subdivision Review Process	5-3
5.5	Conclusions	5-3
Section 6	THE TWELVEMILE CREEK COMPUTER MODEL	6-1
6.1	Existing Stream Characteristics	6-1
6.2	Post-Development Stream Characteristics	6-1

TABLE OF CONTENTS (Continued)

Appendix A

Tables and Plates

Table 14-1	Significant Obstructions
Table 14-2	Storm Drainage Problems
Table 14-3	Proposed Storm Water Collection Systems
Table 14-4	Storm Water Collection and Control Facilities
Table 14-5	Project Development and Construction Schedule and Costs
Table 14-6	Existing Flood Control Projects
Table 14-7	Proposed Flood Control Projects
Table 14-8	Watershed Runoff Data
Table 14-9	Various On-Site Storm Water Control Methods
Table 14-10	Advantages and Disadvantages of Various On-Site Storm Water Control Measures
Plate 14-1	Twelvemile Creek Watershed Base Map
Plate 14-2	Twelvemile Creek Watershed Significant Obstructions Map
Plate 14-3	Twelvemile Creek Watershed Drainage Problem Areas
Plate 14-4	Twelvemile Creek Storm Sewer Systems
Plate 14-5	Twelvemile Creek Watershed Flood Control Projects
Plate 14-6	Twelvemile Creek Watershed Existing Land Use
Plate 14-7	Twelvemile Creek Watershed Ultimate Land Use
Plate 14-8	Twelvemile Creek Watershed Soil Map
Plate 14-9	Twelvemile Creek Watershed 100-Year Flood Plain
Plate 14-10	Twelvemile Creek Watershed Subwatershed Map

Appendix B

Calculations to Determine Increased Runoff and Examples of Specific On-Site Storage

Section I

SUMMARY AND RECOMMENDATIONS

This document has been prepared in accordance with the provisions of the Pennsylvania Storm Water Management Act, P.L. 864, Act 167, October 4, 1978 and is a pilot study under that Act. The Northwest Institute of Research of Erie, Pennsylvania and Woodruff Incorporated, Consulting Engineers of Cleveland, Ohio have formed a consortium for the purpose of developing a pilot storm water management plan for the Lake Erie and Elk Creek Watersheds. This study has been prepared under the direction of the Pennsylvania Department of Environmental Resources, Bureau of Dams and Waterway Management, Division of Storm Water Management and the Erie County Department of Planning.

This report is Volume 14 in a series of 14 volumes prepared for the Erie County Department of Planning. The purposes of this report are:

1. To establish as base conditions the existing land use and the existing storm water runoff in the Twelvemile Creek Watershed against which future conditions can be compared.
2. To calculate the runoff from a projected land use to indicate how much more flow the main stream and its branches would be required to carry.
3. To present a set of criteria and standards for storm water management in this watershed.
4. To recommend the one or more alternative storm water management methods best suited to the needs of the Twelvemile Creek Watershed.

The standards and criteria which are to be applied to storm water runoff have been summarized in Section 4 and are described in complete detail in Volume 1. It is recommended that these standards and criteria be adopted by the committee in the Twelvemile Creek Watershed Area.

The various means of implementing these standards and criteria are discussed in Section 5. It is recommended that the on-site approach to storm water management as described in Section 5 be adopted immediately and included in all future development plans. Immediate steps are to be taken so that the Twelvemile Creek Watershed Area will be prepared for the tremendous growth that will occur should the U.S. Steel proposal for Springfield Township come to fruition.

It should be emphasized that this storm water management plan is intended solely to minimize the creation of new flood problem areas as a result of increased runoff due to development. Also, existing problem areas will not be aggravated by increased runoff. In this way, the municipalities will be able to concentrate on solutions for those flooding problems that presently trouble local property owners.

Section 2

BACKGROUND

The basic approach to storm water management in the past has been to achieve maximum convenience at an individual site by getting rid of any excess surface water after a rainfall as quickly as possible. This removal is accomplished typically by disposal of the water through a storm sewer or other closed system. As the land in a given area becomes more and more developed, this policy has led to the following problems:

1. Flooding due to overland flow.
2. Increasingly frequent downstream flooding.
3. Diminished groundwater supplies.
4. Erosion of stream banks.
5. Siltation and pollution of streams.

As land development continues, the percentage of impervious land surface increases as paved roads, sidewalks, parking lots, and other structures are built. The result of this change is to further aggravate the problem. Areas that previously had no flooding begin experiencing problems and areas which might have been prone to flooding earlier now experience an even more severe problem.

The solution of passing one's own water problems downstream is no longer acceptable. The potential damage created by such an approach cannot be tolerated as developments continue to move into once rural areas.

Clearly, a new approach to handling storm water runoff is needed. A storm water management plan is necessary that protects our land and streams as well as permits reasonable development. The new approach must strike a balance between local convenience and protection against the hazard of flooding. One significant feature of the approach presented in this document will be the planned detention of water on-site in various types of storage facilities. Such structures will hold the water and release it slowly over time, after the danger of flooding is past. In the process, downstream areas will be protected.

This concept will be discussed more fully in the following pages and will be applied to the specific requirements of the Twelvemile Creek Watershed.

Section 3

DESCRIPTION OF THE TWELVEMILE CREEK WATERSHED

On Plate No. 14-1⁽¹⁾ the base map for the Twelvemile Creek Watershed Area is presented. On this map, major topographic features of the watershed are shown. The Twelvemile Creek Watershed is located in the townships of Harborcreek, Greenfield and North East. It covers an area of approximately 8,550 acres.

3.1 Local Input Data

There are five types of local data which have been considered in the description of the Twelvemile Creek Watershed Area. These include:

1. Significant obstructions
2. Existing drainage problems
3. Location of existing storm sewers
4. Proposed storm sewers
5. Existing and proposed flood control projects

Each of these types of data are discussed in the following paragraphs. This information is as complete as possible at the time of writing. Additional information may be added as it becomes available.

3.1.1 Significant obstructions

A significant obstruction is defined as any structure or assembly of materials which might impede, retard or change the flow of storm water runoff.

Significant obstructions in the Twelvemile Creek Watershed were located both by surveys conducted by the consultant and by local input from municipal and county officials as well as the Advisory Committee composed of representatives from the affected municipalities. Those obstructions which were identified are described on Table 14-1 and located on the map presented on Plate No. 14-2.

A total of 13 obstructions were mapped. These include many bridge abutments and piers or culverts through which the main stream or side branches pass as they flow under highways, driveways and railroads. While many of these structures do not obstruct normal flow, all may be considered potentially obstructive during severe storms if debris is allowed to collect in culvert openings or around bridge piers. They also serve as potential entrapments for ice floes.

(1) For the convenience of the reader and to facilitate locating of tables and maps, all of these illustrations are placed in order in Appendix A at the end of this report.

The importance of these obstructions is obvious since anything which interferes with the natural flow of the stream can contribute to local flooding under storm conditions. The control of increased runoff due to development that would result from the implementation of this storm water management plan will insure that these structures will operate hydraulically at their present levels. Thus, if a particular structure has no recurrent problems in passing stream flows at the present time, no problems would be expected in the future under the plan as development proceeds. Flooding problems due to structures of insufficient hydraulic capacity will not get worse in the future, nor will they be eliminated by the institution of these storm water management policies. The intent of this plan is to maintain the status quo regarding stream flow.

3.1.2 Existing drainage problem areas

Plate No. 14-3 locates the three drainage problems identified in the Twelvemile Creek Watershed. The problems are described briefly on Table 14-2.

The first of these problems is located at Brickyard Road just south of Law Road in North East Township. A branch of Twelvemile Creek regularly tops its banks and floods onto the road. The problem here seems to be insufficient channel capacity. The solution might be to increase the size of the channel or to provide some detention facilities in the area.

The second problem listed in Table 14-2 is located on Brickyard Road north of Route 20 in North East Township. The culvert inlet at this point floods during severe rainstorms. The capacity of the existing culvert must be investigated. It will probably be necessary to increase the size of the culvert or provide some form of detention in this area.

The third problem is located in North East Township at the mouth of the creek on Lake Erie. Ice jams are a recurrent problem here and can produce substantial flooding. Under emergency conditions, the responsibility to take corrective action falls first on the local municipality. It is recommended that the local municipalities in this case make advance arrangements with all involved agencies and individuals to obtain all required permits, permission to enter private property, etc. in order to regularly remove ice in the creek.

If the municipalities do not have the means to handle a particular situation, they should turn first to the Erie County Emergency Management Agency. This is presently under the direction of Mr. James Smith (telephone: (814) 454-5811).

Problems that go beyond the capabilities of this agency should be referred to the Pennsylvania Emergency Management Agency, Western Region Office in Indiana, Pennsylvania. This is presently under the direction of Mr. Carl Keuhn (telephone: (814) 357-2990).

The United States Army Corps of Engineers is available for technical assistance only. It is their policy to become further involved only in the most hazardous of cases.

As other drainage problems are identified in the Twelvemile Creek Watershed Area, they can be added to Table 14-2 and Plate No. 14-3.

3.1.3 Existing storm sewers

The third type of local input involved the location of all existing storm sewers in the Twelvemile Creek Watershed Area. These data can be obtained by consulting the Harborcreek Township Comprehensive Plan (June 1980).

At the present time, barring evidence to the contrary, the assumption is made that none of these storm sewers has a significant impact on the management of storm water in this area.

3.1.4 Proposed storm sewers

Tables 14-3, 14-4 and 14-5 are provided for the purpose of listing and locating all proposed storm sewers in the Twelvemile Creek Watershed Area. At the time of writing this report, no new storm sewers are known to have been proposed for the Twelvemile Creek area. The tables are provided so that information can be added to them and Plate No. 14-4 as it becomes available. Further information on storm sewers can be obtained by consulting the Comprehensive Plans for Harborcreek, North East Region, and Greenfield Township.

3.1.5 Existing and proposed flood control projects

Plate No. 14-5 and Tables 14-6 and 14-7 are provided for the purpose of entering the location and description of all existing and proposed flood control projects. At the time of writing, there were no known existing or proposed flood control projects in the Twelvemile Creek Watershed Area. Additional information can be added to these maps as it becomes available.

3.2 Present and Projected Land Use

Present land use is shown on Plate No. 14-6. Existing land use data was taken from the Erie County Land Use Plan Update (June, 1978).

It can be seen from the existing land use map that the watershed area is divided into three relatively equal land uses of open, wooded and cultivated. There is a very small amount of residential land use throughout the subject area. The ultimate land use map indicates that the watershed area is projected to develop generally into the residential-agricultural type land use.

Projected land use was derived from various Erie County projections. This is shown on Plate No. 14-7.

3.3 Soil Types

The various soil types found within the Twelvemile Creek Watershed Area are shown on Plate No. 14-8. These soils include the following:

1. Sandy soils of the lake plain (Rimer-Wauseon-Berrien).
2. Gravelly and sandy soils of the beach ridges (Conotton-Ottawa-Fredon).
3. Deep, medium-textured soils in moderately limy till of the glaciated upland (Erie-Ellery and Alden-Langford).
4. Deep, medium-textured soils of the glaciated upland and the lake plain (Allis-Ellery and Alden).
5. Shallow, medium-textured soils of the glaciated upland and the lake plain (Allis-Ellery and Alden).

3.4 The National Flood Insurance 100-Year Flood Plain

The 100-year flood is defined as the highest level of flooding that is likely to occur on the average, every 100 years. The fact that an area has not flooded recently does not mean it will not do so in the future. The probability of such an occurrence is 1 percent in any given year.

The Flood Plain Management Act, Act 166, October 4, 1978, prohibits development within designated flood plains. No development is allowed in any areas 50 feet or less from the boundaries of designated flood plains. This is intended to reduce flood damage and accumulation of debris due to the 100 year flood and is consistent with the intent of the Storm Water Management Act.

On Plate No. 14-9, the flood plain for the basic or 100-year flood is shown. The information was taken from the National Flood Insurance Program Maps (Available for reference at the Erie County Planning Department office).

Section 4

STANDARDS AND CRITERIA FOR STORM WATER MANAGEMENT

The following are the recommended standards and criteria for storm water management in the Twelvemile Creek Watershed Area. A complete derivation and justification of these standards are to be found in Volume 1 of this study report. The recommended standards and criteria may be completely satisfied by use of the on-site approach discussed in Section 5 of this volume.

The most fundamental standard of this study is that the amount of flow along Twelvemile Creek must not be allowed to increase at the data points labeled "A" through "R" on Plate No. 14-10 above those existing flows indicated on Table 14-8 for each of these points. These flows were obtained from a computer model developed expressly for Twelvemile Creek using the design storm described below. Flows at positions between the given points must not exceed a straight line interpolation of flow values at adjacent points. This will insure that the flow characteristics of Twelvemile Creek will remain at their 1981 level for storms equal to or less than the design storm. The objective is to maintain the existing level of flow in the main stream channel for the design storm and to maintain bank-full capacity for the side branches. A policy such as this will not only effectively manage increased runoff as desired, but will help to maintain the sensitive ecological balance of the stream.

4.1 Definition of Design Storm

The design storm for this study has been determined to be the 10-year, 24-hour storm. The choice of this storm is justified in Volume 1 of this study. The 10-year, 24-hour storm is that theoretical storm of 24-hour duration that statistically will occur once in 10 years. On the average such a storm would produce 4.8 inches of rain in a 24-hour period. As previously mentioned, this is the storm used to derive the magnitude of flow at the data points described above.

4.2 Definition of Type 1 and Type 2 Channels

Because some of the channels that make up the Twelvemile Creek drainage systems are more able to carry increased flows than are others, two sets of criteria and standards have been devised for two types of channels. The first, or Type 1 Channels, are characterized as main stream channels. They have a well-defined flood plain and can handle increased flows very easily. These are the shaded portions of the Twelvemile Creek drainage system shown on Plate No. 14-9, "The One-Hundred-Year Flood Plain." The second are referred to as Type 2 channels. These consist of all the other portions of the Twelvemile Creek drainage system that are not shaded on Plate No. 14-9. They are characterized as branch stream channels. Plate No. 14-10, the Subwatershed Map for Twelvemile Creek, indicates those portions of the watershed area whose runoff is initially discharged into Type 1 Channels and those whose runoff is initially discharged into Type 2 Channels.

4.3 Criteria for Type 1 Channels (Main Stream)

For those sites which are to discharge their runoff into a Type 1 Channel, it will be required that the increased runoff after development (due to the design storm) be managed by any of the recommended on-site methods discussed in Section 5. That is to say, the runoff due to the 10-year, 24-hour storm is to be calculated again for the same storm taking into account the specific proposed development. The difference between these two runoffs is that which must be managed.

4.4 Criteria for Type 2 Channels (Branch Streams)

For those sites which are to discharge their runoff into a Type 2 Channel, a more stringent standard is to be applied. This is necessary because these channels typically are too small to accommodate increased runoff. They have no flood plain to act as a cushion.

In this situation, the amount of storm water that must be stored is the difference in runoff between that due to proposed land use for the 10-year, 24-hour storm and that due to the mean annual storm for existing land use conditions. As defined previously, the mean annual storm ⁽¹⁾ is calculated by taking the largest storm for each year on record and averaging them together. Statistically, the mean annual storm is equivalent to a storm with a return frequency of 2.33 years. Whereas side branches are naturally formed to handle the more frequent mean annual storm, this more stringent criterion would now protect them against flooding for all storms up to and including the 10-year, 24-hour storm.

(1)The concept of a mean annual storm was developed by L. Leopold and referenced in Storm Water Management, 1980.

Section 5

IMPLEMENTATION

5.1 Introduction

Every parcel of land has unique storm water runoff characteristics which inevitably change when the parcel is developed, usually resulting in an increase in storm water runoff from the site. When development takes place the increase in storm water runoff is magnified and serious problems can result. Prior to the development of this Plan there was no established method through which a municipality could require developers to take precautions against causing storm water runoff problems. The purpose of this Plan is to help correct the situation by establishing standards for storm water management and an administrative procedure whereby those standards can be applied by local governments to development within their jurisdiction.

The Storm Water Management Plan will be implemented by individual municipalities through the adoption of a storm water management ordinance or through amendments to existing subdivision or zoning regulations. Administration of the storm water management program will be accomplished through a combination of enforcement actions undertaken through the building permit process and through the subdivision review process, both of which are detailed later in this Section.

5.2 Special Considerations

Prior to discussing the specifics of the Building Permit Process and the Subdivision Review Process, two subjects which fall outside of the scope of this Plan's evaluation procedures will be discussed. The Building Permit and Subdivision Review evaluation procedures for storm water management apply to all forms of development and land use except development in areas with an existing storm sewer infrastructure and with respect to agricultural land.

In situations where development or redevelopment occurs in an area where direct access to an established storm sewer infrastructure is possible, the development or redevelopment is considered sufficient to manage its storm water runoff if its on-site storm drainage network is incorporated into the existing storm water infrastructure. By connecting with the existing storm sewer system, the development would be relieved of further obligations to manage storm water runoff in accordance with this Plan unless the municipal governing body perceives a potential storm water drainage problem or if the governing body wishes to correct an existing storm drainage problem. In these cases where the governing body desires a more stringent application of storm water management controls they may require that a detention/retention plan be developed which would alleviate the storm water drainage problem.

Evaluating agricultural land for compliance with storm water management controls is the second topic which falls outside of the scope of the Building Permit and Subdivision Review procedures. With respect to agricultural land, the recommended method of storm water management is to have a Soil Erosion and Sedimentation Control plan and/or permit prepared in accordance with existing State law and reviewed by the Erie County Soil Conservation Service. This applies only to cultivated land; agricultural accessory structures and residential structures should be evaluated by the municipality through the applicable method as outlined in the following sections.

5.3 Building Permit Process

If a proposed subdivision is defined by the host municipality's subdivision regulations as a minor subdivision (usually 10 lots or less) or if development is proposed involving no subdivision of property, then storm water management standards and criteria should be evaluated at the time when development is formally proposed via an application for a building permit. This system is designed so that smaller developments may occur without incurring added engineering expense and so that municipalities can implement storm water management requirements without incurring substantial administrative overhead expense.

The recommended technique to be followed when evaluating a minor subdivision or a development on an existing lot of record is presented here. First, all developments which fall into the above categories must meet each of the following:

Standard Controls

1. Roof drains are not to be connected to streets, sanitary sewers or roadside ditches.
2. Runoff from the impervious areas must be drained to the pervious areas of the property.
3. Runoff is not to be collected or concentrated into an artificial conveyance and discharged onto adjacent property.

Next, the zoning officer must calculate the percentage of the parcel which will be covered by impervious surfaces after development is concluded. In this context impervious surfaces mean all land covered by a house, barn, garage, patio, driveway, etc. Information needed to calculate the percentage of impervious area should be readily available on the building permit application. Once the calculation is made the zoning officer should refer to the following table to determine how many storm water controls in addition to those listed above will be needed to comply with the standards of the Storm Water Management Plan. The additional controls can be found in Table 14-9.

Determination of Controls

Less than 15% impervious	Standard controls only
15% - 19.99% impervious	Standard controls only plus one additional control
20% - 24.99% impervious	Standard controls plus 2 additional controls
25% - 30% impervious	Standard controls plus 3 additional controls

The methodology outlined above is designed to be used for a proposed development which covers 30% or less of the parcel with an impervious surface. Under such circumstances the zoning officer can show the potential developer what storm water management controls are needed in order to receive this building permit. If the proposed development will cover greater than 30% of the parcel with an impervious surface or if the total impervious area exceeds one acre, then a licensed professional must be consulted to prepare a detention/retention plan which meets the approval of the governing body. An additional fee is recommended to be added to the existing building permit fee to cover the expense of administering the program.

5.4 Subdivision Review Process

If a development is defined by the host municipality's subdivision regulations as a major subdivision (usually more than 10 lots), the storm water management standards and criteria should be evaluated during the subdivision review process. This use of the subdivision review process is designed to ensure that large scale developments employ proper techniques to control storm water runoff and that these controls are firmly established prior to municipal or county approval of the subdivision plat. When a preliminary major subdivision plan is submitted for municipal review it shall be accompanied by detailed storm water detention/retention specifications which meet the criteria of the Plan and which have been prepared by a professional licensed to perform such work in this Commonwealth. The proposed storm water detention/retention specifications shall be reviewed by the municipality and/or its engineer and shall satisfy the municipality before the major subdivision plan is approved. The municipality may require controls which are more stringent than those which meet the Storm Water Plan's criteria if circumstances dictate that such measures are needed to alleviate a current drainage problem or a suspected future drainage problem.

5.5 Conclusion

The Lake Erie and Elk Creek Storm Water Management Plan has been developed in accordance with Act 167 of 1978, the Pennsylvania Storm Water Management Act. Under the provisions of this Act, municipalities are granted certain powers and must assume certain responsibilities. One of the responsibilities which has been assigned to local governments by the Act is the responsibility to adopt implementing ordinances such as those described in this section. Another responsibility assigned to the municipality is that of properly enforcing the storm water management ordinances and regulations. Because of the responsibilities awarded to municipalities under Act 167, each municipality affected by this Plan should consult their municipal solicitor for a briefing about the extent of their obligations under the provisions of Act 167.

Section 6

THE TWELVEMILE CREEK COMPUTER MODEL

As has been discussed previously, a computer model of the Twelvemile Creek drainage system was developed for the purpose of this study. A complete description of the background and development of this computer model is given in Volume 1 of this report. The following is a summary of the data used as input for the model and a description of the data it yielded as output.

6.1 Existing Stream Characteristics

The existing land use for the Twelvemile Creek Watershed Area is shown on Plate No. 14-6. This is a base land use against which future development is to be compared upon adoption of this storm water management plan. It can be seen that the area is generally rural with some residential and commercial development.

The runoff due to this land use was entered into the computer model. A soil factor derived from the various types of soils found in the Twelvemile Creek Watershed Area, as shown on Plate No. 14-8, was also taken into account. The results of the computer output are summarized on Table 14-8. The flow characteristics of Twelvemile Creek due to the runoff from existing land use are shown in the first columns labeled "Existing Runoff" for various data points. These data points are located on Plate No. 14-10. These are the flow characteristics of the stream which must not be altered due to the development of land in the watershed area.

6.2 Post-Development Stream Characteristics

A projected ultimate land use for the Twelvemile Creek Watershed Area was taken from the Erie County Land Use Plan Update (June, 1978). It is shown on Plate No. 14-7. This projection assumed that all of Erie County would develop to its maximum potential, as it would if U.S. Steel were to build the large steel producing facility it has proposed for Springfield Township. Projections indicate major growth in residential-agricultural usage.

The runoff due to this projected land use was entered into the computer model. Again, a soil factor was taken into account. The resultant flow characteristics at the data points are shown in the column labeled "Ultimate Runoff" in Table 14-8.

It can be seen that the peak flow of the ultimate runoff is considerably higher at all points than is that of the existing runoff. For example, at the outlet to Lake Erie, the peak flow is calculated to be 7,072 cubic feet per second (cfs) for existing runoff and 8,243 cfs for ultimate runoff.

The depth of the ultimate flow is substantially higher at all data points. The increased depth becomes more critical in upstream reaches of the watershed. This implies a greater risk of flooding in portions of the channel that have a naturally smaller cross section. These are generally the branch of Type 2 Channels.

The velocity of the flow can also be seen to be much higher for ultimate runoff than for existing runoff. This is an undesirable situation that could result in excessive erosion of the stream bed. The stream channels would eventually widen and deepen beyond their present limits and possibly interfere with development along their banks. Foundations for bridges, culverts or retaining walls might be undermined due to a process known as scour. Scour is the washing away of earth around the footings of piers, bridge abutments retaining walls or the like, and in the process, exposing them. This reduces their structural stability.

Water quality would decline due to the inordinant amount of soil particles being carried along by the current. Development would decrease the absorption of rainfall due to the amount of impervious cover it would probably bring with it. This could lower the groundwater table to unacceptable levels.

The COWAMP Study Area 7 Report, prepared by the Department of Environmental Resources of the Commonwealth of Pennsylvania does not reveal any of the above to be current problems for the Eightmile Creek Watershed Area. This makes it very important to maintain existing water quality standards related to storm water runoff.

In addition, the Clean Streams Law of Pennsylvania regulates activities that affect any stream in the Commonwealth in order to preserve and improve the purity of their water. The Storm Water Management Act will aid in the attainment of these objectives. All work done to manage storm water must be done in compliance with these rules and regulations.

APPENDIX A
TABLES AND PLATES

PLAN NO.

SWM 25-31
TWELVEMILE CREEK
TABLE 14-1

WOODRUFF, INC.
CONSULTING ENGINEERS

01111607
01111606

STORM DRAINAGE PROBLEMS

NO.	LOCATION	MUNICIPALITY	PROBLEM	PROPOSED SOLUTION
1	On River Road and Twelve Mile Creek (Branch)	Northwest Township	Water Flows Onto Road As the River Rises, Stream Bed	Improve Channel Cross Sections
2	Brickyard Road and Twelve Mile Creek (Branch)	Northwest Township	Flooding of Culvert & Inlet During Heavy Rainstorm	Increase Culvert Size, Increase Channel Capacity
3	Water Line Outlet of Twelve Mile Creek	Northwest Township	Ice Jams The Mouth of the Creek	Construct Upstream Retention Facility, Make Advance Arrangements With St. Johns River Water Control District, or Individuals to Regularly Remove Ice.

PLAN NO.

PLAN NO.

A large, stylized, cartoonish letter 'A' with a face, arms, and legs, positioned diagonally across the page. The 'A' is white with a black outline and is set against a background of horizontal lines. It has a smiling face with two eyes and a mouth, and its arms and legs are also outlined in black. The 'A' is tilted at an angle, running from the top left towards the bottom right.

FOZ

WOODRUFF, INC.

**SWM 2631
TWELVEMILE CREEK**

TABLE 14-3

PLAN NO.

WOODRUFF, INC.
CONTINUING IMMERSION
CINCINNATI OHIO

PLAN NO

WOODRUFF, INC.
CONSISTING OF
CLEVELAND OHIO

**SWM 2531
TWELVEMILE CREEK**

TABLE 14-7

WATERSHED RUNOFF DATA

LOCATION	EXISTING RUNOFF				ULTIMATE RUNOFF				ULTIMATE RUNOFF WITH STORAGE						
	PEAK FLOW C.F.S.	TIME OF PEAK HR.	DEPTH FT.	VELOCITY FPS	VOLUME MIL. CU. FT.	PEAK FLOW C.F.S.	TIME OF PEAK HR.	DEPTH FT.	VELOCITY FPS	VOLUME MIL. CU. FT.	PEAK FLOW C.F.S.	TIME OF PEAK HR.	DEPTH FT.	VELOCITY FPS	VOLUME MIL. CU. FT.
A. Branch	653	71				770	71								
Upstream	624	72				747	72								
Downstream	1265	71	3.13	14.20		1341	71	3.69	15.01						
B. Branch	209	70				234	70								
Upstream	1909	72				2032	72								
Downstream	2033	72	3.44	14.38		2473	72	3.70	15.41						
C. Branch	646	70				719	70								
Upstream	2037	72				2504	71								
Downstream	2721	71	3.79	15.46		3112	71	4.15	16.27						
D. Downstream	3415	72	3.33	13.73		3933	72	4.29	17.57						
E. Downstream	3506	72	3.99	12.19		4203	72	4.56	18.33						
F. Branch	359	70				377	70								
Upstream	9819	73				4227	73								
Downstream	3832	73	3.23	11.23		4463	72	4.00	11.64						
G. Branch	705	71				756	71								
Upstream	3351	73				4502	73								
Downstream	4573	72	5.13	13.03		5106	72	5.59	13.67						
H. Branch	4456	74				1710	73								
Upstream	5395	74				5131	74								
Downstream	1159	74	6.99	13.42		6361	73	7.57	14.44						
I. Branch	5903	74				1303	74								
Upstream	7041	74				8470	73								
Downstream	558	70	6.79	14.61		8477	74	7.96	17.07						
K. Downstream	432	70	2.25	11.13		650	70	3.83	11.67						
L. Downstream	507	70	3.00	10.58		724	70	2.41	11.03						
M. Downstream	594	73	2.93	12.03		574	70	3.17	12.43						
N. Downstream	885	72	3.72	12.37		712	72	3.17	12.33						
O. Downstream	1193	72	4.09	13.05		1059	72	4.05	13.96						
P. Downstream	333	71	2.69	9.53		1392	72	4.40	13.59						
Q. Downstream	403	71	3.71	7.71		581	71	2.84	9.03						
R. Downstream	972	73	4.43	10.27		514	73	3.93	7.92						
Loss	7072	75				6249	74								

SWM 2531
TWELVEMILE CREEK

TABLE 144

Table 14-9

VARIOUS ON-SITE STORM WATER CONTROL METHODS

AREA	REDUCING RUNOFF	DELAYING RUNOFF
Large Flat Roof	<ol style="list-style-type: none"> 1. Cistern storage 2. Rooftop gardens 3. Pool storage or fountain storage 	<ol style="list-style-type: none"> 1. Ponding on roof by constricted downspouts 2. Increasing roof roughness <ol style="list-style-type: none"> a. Rippled roof b. Gravelled roof
Parking Lots	<ol style="list-style-type: none"> 1. Porous pavement <ol style="list-style-type: none"> a. Gravel parking lots b. Porous or punctured asphalt 2. Concrete vaults and cisterns beneath parking lots in high value areas 3. Vegetated ponding areas around parking lots 4. Gravel trenches 	<ol style="list-style-type: none"> 1. Grassy strips on parking lots 2. Grassed waterways draining parking lot 3. Ponding and detention measures for impervious areas <ol style="list-style-type: none"> a. Rippled pavement b. Depressions c. Basins
Residential	<ol style="list-style-type: none"> 1. Cisterns for individual homes or groups of homes 2. Gravel driveways (porous) 3. Contoured landscape 4. Ground-water recharge <ol style="list-style-type: none"> a. Perforated pipe b. Gravel (sand) c. Trench d. Porous pipe e. Dry wells 5. Vegetated depressions 	<ol style="list-style-type: none"> 1. Reservoir of detention basin 2. Planting a high delaying grass (high roughness) 3. Gravel driveways 4. Grassy gutters or channels 5. Increased length of travel of runoff by means of gutters, diversions, etc.
General	<ol style="list-style-type: none"> 1. Gravel alleys 2. Porous sidewalks 3. Mulched planters 	<ol style="list-style-type: none"> 1. Gravel alleys

Source: Urban Hydrology for Small Watersheds.
 Technical Release No. 55

Table 14-10

ADVANTAGES AND DISADVANTAGES OF VARIOUS
ON-SITE STORM WATER CONTROL METHODS



MEASURE	ADVANTAGES	DISADVANTAGES
A. Cisterns and Covered Ponds	<ol style="list-style-type: none"> 1. Water may be used for: <ol style="list-style-type: none"> a. Fire Protection b. Watering lawns c. Industrial processes d. Cooling purposes 2. Reduce runoff while only occupying small area 3. Land or space above cistern may be used for other purposes 	<ol style="list-style-type: none"> 1. Expensive to install 2. Cost required may be restrictive if the cistern must accept water from large drainage areas 3. Requires slight maintenance 4. Restricted access 5. Reduces available space in basements for other uses
B. Rooftop Gardens	<ol style="list-style-type: none"> 1. Esthetically pleasing 2. Runoff reduction 3. Reduce noise levels 4. Wildlife enhancement 	<ol style="list-style-type: none"> 1. Higher structural loadings on roof and building 2. Expensive to install and maintain
C. Surface Pond Storage (usually residential areas)	<ol style="list-style-type: none"> 1. Controls large drainage areas with low release 2. Esthetically pleasing 3. Possible recreation benefits <ol style="list-style-type: none"> a. Boating b. Ice skating c. Fishing d. Swimming 4. Aquatic life habitat 5. Increases land value of adjoining property 	<ol style="list-style-type: none"> 1. Requires large areas 2. Possible pollution from storm water and siltation 3. Possible mosquito breeding areas 4. May have adverse algal blooms as a result of eutrophication 5. Possible drowning 6. Maintenance problems

Table 14-10 (Continued)

D. Ponding on Roof by Constricted Downspouts	<ol style="list-style-type: none"> 1. Runoff delay 2. Cooling effect for building <ol style="list-style-type: none"> a. Water on roof b. Circulation through 3. Roof ponding provides fire protection for building (roof water may be trapped in case of fire) 	<ol style="list-style-type: none"> 1. Higher structural loadings 2. Clogging of constricted inlet requiring maintenance 3. Freezing during winter (expansion) 4. Waves and wave loading 5. Leakage of roof water into building (water damage)
E. Increased Roof Roughness <ol style="list-style-type: none"> a. Rippled roof b. Gravel on roof 	<ol style="list-style-type: none"> 1. Runoff delay and some reduction (detention in ripples or gravel) 	<ol style="list-style-type: none"> 1. Somewhat higher structural loadings
F. Porous pavement (parking lots and alleys) <ol style="list-style-type: none"> a. Gravel parking lot b. Holes in impervious pavements ($\frac{1}{4}$ in. diam.) filled with sand 	<ol style="list-style-type: none"> 1. Runoff reduction (a and b) 2. Potential groundwater recharge (a and b) 3. Gravel pavements may be cheaper than asphalt or concrete (a) 	<ol style="list-style-type: none"> 1. Clogging of holes or gravel pores (a and b) 2. Compaction of earth below pavement or gravel decreases permeability of soil (a and b) 3. Ground-water pollution from salt in winter (a and b) 4. Frost heaving for impervious pavement with holes (b) 5. Difficult to maintain 6. Grass or weeds could grow in porous pavement (a and b)
G. Grassed channels and vegetated strips	<ol style="list-style-type: none"> 1. Runoff delay 2. Some runoff reduction (infiltration recharge) 3. Esthetically pleasing <ol style="list-style-type: none"> a. Flowers b. Trees 	<ol style="list-style-type: none"> 1. Sacrifice some land area for vegetated strips 2. Grassed areas must be mowed or cut periodically (maintenance costs)

Table 14-10(Continued)

H. Ponding and detention measures on impervious pavement	1. Runoff delay (a, b, and c) 2. Runoff reduction (a and b)	1. Somewhat restricted movement of vehicle (a) 2. Interferes with normal use (a and c) 3. Damage to rippled pavement during snow removal (a) 4. Depressions collect dirt and debris (a, b, and c)
a. Rippled pavement		
b. Basins		
c. Constructed inlets		
I. Reservoir or detention basin	1. Runoff delay 2. Recreation benefits a. Ice Skating b. Baseball, football, etc. if land is provided 3. Esthetically pleasing 4. Could control large drainage areas with low release	1. Considerable amount of land is necessary 2. Maintenance costs a. Mowing grass b. Herbicides c. Cleaning periodically (silt removal) 3. Mosquito breeding area 4. Siltation in basin
J. Converted septic tank for storage and ground-water recharge	1. Low installation costs 2. Runoff reduction (infiltration and storage) 3. Water may be used for: a. Fire protection b. Watering lawns and gardens c. Ground-water recharge	1. Requires periodic maintenance (silt removal) 2. Possible health hazard 3. Sometimes requires a pump for emptying after storm
K. Ground-water recharge	1. Runoff reduction (infiltration) 2. Ground-water recharge with relatively clean water 3. May supply water to garden or dry areas 4. Little evaporation loss	1. Clogging of pores or perforated pipe 2. Initial expense of installation (materials)
a. Perforated pipe or hose		
b. French drain		
c. Porous pipe		
d. Dry well		
L. High delay grass (high roughness)	1. Runoff delay 2. Increased infiltration	1. Possible erosion or scour 2. Standing water on lawn in depressions




SWM 25 31
TWELVEMILE CREEK WATERSH.
BASE MAP


PLATE NUMBER 14-1




WOODRUFF, INC.
CONSULTING ENGINEERS
1000 BROADWAY
NEW YORK, N.Y. 10003




Lake Erie



SWM 2531
TWELVEMILE CREEK WATERSHED
SIGNIFICANT OBSTRUCTIONS MAP



WOODRUFF, INC.
CONSULTING ENGINEERS
CINCINNATI, OHIO



SWM 2531
TWELVEMILE CREEK
STORM SEWER SYSTEMS

WOODRUFF, INC.
CONSULTING ENGINEERS
CLEVELAND, OHIO




LAKE ERGE

HARBORCREEK

GREENFIELD


NORTH EAST



SWM 2531
TWELVEMILE CREEK WATERSHED
FLOOD CONTROL PROJECTS




WOODRUFF, INC.
CONSULTING ENGINEERS
CINCINNATI, OHIO




SUBWATERSHED NUMBER	WEIGHTED CN FOR EXISTING LAND USE
1	74.86
2	74.36
3	75.90
4	76.26
5	76.23
6	76.19
7	76.40
8	76.16
9	75.28
10	75.62
11	77.78
12	76.22
13	74.23
14	77.45
15	74.22
16	65.96
17	74.96
18	75.68
19	75.25
20	71.32
21	76.19
22	72.35
23	68.61
24	68.12
25	72.68
26	70.37

- EXISTING LAND USE LEGEND
- OPEN
 - WOODED
 - CULTIVATED
 - RESIDENTIAL
 - COMMERCIAL
 - INDUSTRIAL




SWN 25.31
TWELVEMILE CREEK WATERSHED
EXISTING LAND USE

WOODRUFF, INC.
CONSULTING ENGINEERS
CINCINNATI, OHIO



SUBWATERSHED NUMBER	WEIGHTED CN FOR EXISTING LAND USE
1	78.90
2	78.90
3	78.90
4	78.67
5	78.70
6	78.90
7	79.64
8	79.58
9	78.82
10	78.83
11	78.28
12	68.12
13	79.52
14	79.68
15	72.91
16	68.46
17	79.74
18	79.56
19	78.09
20	72.80
21	79.57
22	78.84
23	71.51
24	71.50
25	72.74
26	75.54





- ULTIMATE LAND USE LEGEND
- RESIDENTIAL - AGRICULTURAL
 - WOODED
 - RESIDENTIAL
 - COMMERCIAL
 - INDUSTRIAL



SWM 25/31
TWELVEMILE CREEK WATERSH.
ULTIMATE LAND USE

WOODRUFF, INC.
CONSULTING ENGINEERS
CLAYTON, OHIO



LEGEND

	Sandy soils of the lake plain (Rimer-Wauson-Berrien).	Soil Number 2
	Gravelly and sandy soils of the beach ridges (Conotton-Ottawa-Fredon).	Soil Number 3
	Deep, medium-textured soils in moderately limy till of the glaciated upland (Erie-Ellery and Alden-Langford).	Soil Number 5
	Deep, medium-textured soils in slightly limy till of the glaciated upland (Volusia-Mardin).	Soil Number 6
	Shallow medium-textured soils of the glaciated upland and the lake plain (Allis-Ellery and Alden).	Soil Number 9



SWM 2531
TWELVEMILE CREEK WATERSHE:
SOIL MAP

WOODRUFF, INC.
CONSULTING ENGINEERS
CINCINNATI, OHIO



LAKE ERSE

HARBORCREEK

GREENFIELD

NORTH EAST

LEGEND
THE 100-YEAR FLOOD PLAIN AS DERIVED FROM
THE NATIONAL FLOOD INSURANCE PROGRAM MAPS




WOODRUFF, INC.

CREATING THE FUTURE


SWIM 1531
TWELVEMILE CREEK WATERS
100 YEAR FLOOD

NOT TO SCALE 1:50,000



NOTE: THE SYMBOL BELOW IS USED TO LOCATE THE DATA POINTS LISTED ON THE WATERSHED RUNOFF DATA CHART (TABLE A-8).

SUBWATERSHED NUMBER	AREA ACRES	TIME OF CONCENTRATION MINUTES
1	623.22	40.62
2	478.96	23.35
3	101.63	22.76
4	632.30	33.26
5	173.06	26.74
6	56.63	12.72
7	535.99	27.70
8	707.09	41.25
9	130.29	17.63
10	201.47	38.48
11	284.08	29.23
12	60.30	37.94
13	193.76	13.29
14	227.43	25.98
15	178.46	24.70
16	248.35	43.13
17	640.38	50.51
18	322.12	33.41
19	370.38	33.60
20	395.71	35.10
21	299.67	37.34
22	134.99	24.05
23	200.35	54.88
24	344.67	37.07
25	94.08	8.33
26	367.32	27.63
TOTAL WATERSHED AREA IN ACRES		8559.45



LEGEND
 AREAS THAT DRAIN INTO TYPE 1 CHANNELS
 AREAS THAT DRAIN INTO TYPE 2 CHANNELS



SWM 3531
 TWELVEMILE CREEK WATERSHED
 SUBWATERSHED

WOODRUFF, INC.
 CONSULTING ENGINEERS
 1000 W. 10TH AVE., SUITE 100
 DENVER, CO 80202

APPENDIX B

Calculations To Determine Increased Runoff

And

Examples Of Specific On-Site Storage

APPENDIX B

CALCULATIONS TO DETERMINE INCREASED RUNOFF AND EXAMPLES OF SPECIFIC ON-SITE STORAGE

The procedures presented in this appendix are applicable to all unit developments which contain between 2500 square feet and 43,560 square feet of impervious surface area. Those exempt cases discussed in the text need not make the following calculations. Developments with more than 43,560 square feet of impervious surface area must consult a qualified professional person to aid in determining their excess storm water runoff volume.

By following these methods, the non-technical individual can easily determine the amount of excess storm water runoff which he is required to manage. The methods of control presented in this study, or any other approved innovative methods, may be used to manage this calculated runoff volume.

Excess Storm Water Runoff Calculation Procedure

- Step 1 Determine dimensions of proposed buildings, drives, patios or other impervious areas. These can usually be found on building site plans.
- Step 2 Calculate impervious area. The more common shapes that will be encountered are rectangles, triangles or circles. Equations to calculate the areas of these shapes are as follows: (all dimensions are assumed to be in feet)
- i) Rectangle: $\text{area (sq. ft.)} = \text{length (ft.)} \times \text{width (ft.)}$
 - ii) Triangle: $\text{area (sq. ft.)} = 1/2 \times \text{base (ft.)} \times \text{height (ft.)}$
 - iii) Circle: $\text{area (sq. ft.)} = 0.785 \times \text{diameter}^2 \text{ (ft.)}$
- Step 3 Refer to Section 4.2 and plate of volume describing the watershed in which construction is to take place. If construction is found to be along a Type 1 channel, then use Type 1 criteria. All others use Type 2 criteria.
- Step 4 Use Figure B-1 to find excess runoff volume to be managed.

Example: Figure B-2 shows a typical site plan for proposed residential lot located along a Type 1 Channel. Determine the amount of excess runoff volume required to be managed.

- (1) Dimensions as shown on Figure B-2.

(2) Impervious Area:

- (a) Drive: $14' \times 70' = 980$ sq. ft.
- (b) House: $40' \times 80' = 3200$ sq. ft.
- (c) Patio: $1/2' \times 20' \times 20' = 400$ sq. ft.

Total Impervious Area 6180 sq. ft.

(3.) Type 1 criteria as given.

(4.) From Figure B-1, excess runoff volume to be managed is 1150 cubic feet.

Note: One acre contains 43,560 sq. ft. One cubic foot contains 7.48 gallons of water.

FIGURE B-1




FIGURE B-2
TYPICAL RESIDENTIAL SITE PLAN




FIGURE B-3
ON-SITE STORM WATER MANAGEMENT
ALTERNATE NO. 1
SURFACE STORAGE




FIGURE B-4
ON-SITE STORM WATER MANAGEMENT
ALTERNATE NO.2
OVERSIZED STORM SEWER PIPE




FIGURE B-5
ON-SITE STORM WATER MANAGEMENT
ALTERNATE NO.3
POND STORAGE




FIGURE B-6
ON-SITE STORM WATER MANAGEMENT
ALTERNATE NO. 4
UNDERGROUND TANK STORAGE

